AS-BUILT DRAWING

SCALE 1:50

0 1 2 3 4 5m

±0.000=10.45m ABOVE SEA LEVEL

Legend

- Reinforced Concrete
- Lean Concrete
- Solid Brick Masonry
- Hollow Brick Masonry
- Ventilation Opening

B06/05 Room Number
FT 3 Floor Type 3 (Epoxy Floor)
FFL +0000 Finished Floor Level
W2 Wooden Window 2 (Locally manufactured)
DW1 Wooden Door Window 1 (Locally manufactured)
V1 Wooden Ventilation 1 (Locally manufactured)
D7 Hörmann Doors 7 (Imported)

REFERENCES

DOCUMENT No.	DESCRIPTION

REVISIONS

No.	CHECK	APPR	DATE	DESCRIPTION
A				
B				
C				
D				
E				
F	REI		06.06.08	ADDED WALLS

SONJA KILL
MEMORIAL HOSPITAL FOR CHILDREN
KAMPOT CAMBODIA

Architekt
Hans Haff
Pfarrer-Palm-Straße 17
D-53639 Königswinter
Tel. +49 2244 7188 mail hollandforumbike@gmx.de

CONSULTING ENGINEERS
MEKONG LTD
www.ill-1-consult.com

	NAME	DATE
Prep.	HMR	06.06.08
Check	REI	06.06.08
Chief Eng.		
P.Mgr.		

SUPERSEDED BY DWG. No.

OPD (B06)
FLOOR PLAN
MIDDLE

PROJECT No.	ORIG. SIZE	ORIG. SCALE	DRAWING No.	REV.
602	A0+190	1:50	D-B06-AT-03	

Slope 1:100

Ablagebord
Sysmex Gerinnungs-Automat
Mikroskop
Ablagetisch fahrbar
Ruhezone
Patientenliege
Patientenstuhl
Zentrifuge (große Zentrif.)
Brutgasgerät
Brutschrank Aufschgerät
Funktionsschrankanlage
Funktionswandregalanlage
Arbeitstischanlage
Medikamenten-Kühlschränke
Hängeschränke
Röntgenfilm-betrachter
Wandgarderobenleiste
Untersuchungsleuchte

B06/53 FT 3 FFL ±0000 — Blood Donation Room 3040 X 3795
B06/54 FT 1 FFL ±0000 — Pharmacy / Drugstore 5515 X 7190
B06/55 FT 1 FFL ±0000
B06/56 FT 2 FFL ±0000 — Hall
B06/58 FT 1 — WC/Utility Room
B06/59 FT 1 FFL ±0000 — Drug Expenditure 2365 X 3795
B06/48 FT 3 FFL ±0000 — Blood Bank 2570 X 2870
B06/51 FT 3 FFL ±0000 — Preparation 2540 X 2870
B06/52 FT 3 FFL ±0000 — Blood Sample Taking Room 2945 X 2870
B06/85 FT 1 FFL ±0000 — Doctor's Room 4123 X 2775
B06/86 FT 1 — WC
B06/88 FT 3 FFL ±0000 — Internal Corridor
B06/89 FT 1 FFL ±0000 — Meeting Room 3650 X 5365
B06/90 FT 1 FFL ±0000 — Storage 3650 X 2915
B06/91 FT 1 FFL ±0000 — Staff Room 5237 X 2775
B06/92 FT 1 FFL ±0000 — Clean Utility 2561 X 2775
B06/93 FT 3 FFL ±0000 — Internal Corridor
B06/94 FT 1 FFL ±0000 — Archive 3705 X 2252
B06/95 FT 3 FFL ±0000 — Gypsum 3256 X 3428
B06/97 FT 1 FFL ±0000 — Dirty Utility 2561 X 2775
B06/87 FT 2 FFL ±0000 — Corridor
B06/111 FT 2 FFL ±0000 — Corridor
B06/15 FT 2 — Waiting Area
B06/61 FT 2 FFL ±0000 — Office 8190 x 6093
B06/62 FT 2 FFL ±0000 — Personal 2850x3145
B06/63 FT 2 FFL ±0000 — Internal Corridor
B06/64 FT 2 FFL ±0000 — Head Nurse's Office 3795 x 3050
B06/65 FT 2 FFL ±0000 — Personnel Chief Office 3795 x 3005
B06/66 FT 2 FFL ±0000 — Secretariat
B06/67 FT 2 FFL ±0000 — Administrative Head Office 3795 x 3047
B06/68 FT 2 FFL ±0000 — Storage Room
B06/72 FT 1 — WC
B06/73 FT 2 FFL ±0000 — Cashier's Office 3795 x 2975
B06/74 FT 1 — WC-Female 2005x3065
B06/77 FT 1 — Disabled WC 1530x3065
B06/78 FT 1 FFL -0025 — Utility Rm. 1500x3065
B06/79 FT 1 FFL -0025 — WC-Male 2805 x3065
B06/84 FT 2 FFL ±0000 — Conference Meeting 8190 x 15645
B06/04 FT 2 FFL ±0000 — Storage
B06/03 FT 2 FFL ±0000 — Secretariat 3625x3069
B06/06 FT 1 — WC
B06/17a FT 2 — Internal Corridor
B06/10 FT 2 FFL ±0000 — Senior Consultant 2 3780x3840
B06/09 FT 2 FFL ±0000 — Senior Consultant 3 3780x3840
B06/05 FT 2 FFL ±0000 — Hall
B06/137 FT 1 FFL ±0000 — Mechanical Service Room
B06/138 FT 1 FFL ±0000 — Archive 1962x2870
B06/139 FT 1 — Corridor
B06/140 FT 1 FFL ±0000 — Office 1867 x 3780
B06/135 FT 3 FFL ±0000 — Examination Rm 1 3743 x 5140
B06/110 FT 2 — Waiting Area

D5.10 D9.6 D3 D3a D5.3 D5.4 D5.5 D5.6 D5.12 D11a D6.6 D6.8 D6.10 D9.2 D9.12 D6.9 D13.15 FFL -0025 D21.1 D21.2 D2d D1.11 D11.36 D7

W1 W2 W2a W3 W3a W12 W13 W15

Slope 1:100 1:100

D A/14

E A/15

K A/19

Wooden grill

6 7 8 9 10 11